

AA DRYWALL CONSTRUCTION, LLC

DRYWALL • METAL FRAMING • INSULATION • FINISHES

The Residences at Claude Pepper

750 NW 18th Terrace • Miami, Florida 33136

MATERIAL SUBMITTAL PACKAGE

REVISION 1 — JOB-SPECIFIC RESUBMITTAL

PROJECT	The Residences at Claude Pepper (RACP) — 15-Story Multifamily Residential, 428 Units + Community Center
OWNER / DEVELOPER	Related Urban Development Group
CONSTRUCTION MANAGER	Related Group — Attn: Juan Caffroni, Sr. Construction Manager 2850 Tigertail Ave., Suite 800, Miami, FL 33133
ARCHITECT	Cohen • Freedman • Encinosa & Assoc. Architects, P.A. 8085 NW 155th Street, Miami Lakes, FL 33016
SUBCONTRACTOR	AA Drywall Construction, LLC 12951 SW 124th Street, Miami, FL 33186 • Office (305) 238-7900
SCOPE / SPEC SECTIONS	09 22 16 Non-Structural Metal Framing • 09 29 00 Gypsum Board • 07 21 00 Thermal Insulation • 07 84 00 Firestopping
DRAWING REFERENCES	A8.01 Wall Types – Concrete • A8.02 Wall Types – Framing • Level Plans (Permit Set 09/15/2025)
SUBMITTAL NO. / DATE	09 29 00–01, Rev. 1 • July 14, 2026

REVISED & RESUBMITTED PER CM REVIEW COMMENTS

All products in this package are tagged with their specific location of use (residential units, corridors, wet walls, showers/tubs, ceilings, exterior walls) and keyed to the project wall types. Manufacturer data sheets follow each section divider. Only products intended for installation on this project are included.

Submittal Transmittal & Response to Review Comments

THE RESIDENCES AT CLAUDE PEPPER — SUBMITTAL 09 29 00-01, REV. 1

To: Juan Caffroni, Sr. Construction Manager — Related Group

From: AA Drywall Construction, LLC

Re: Drywall / Metal Framing / Insulation / Firestopping Material Submittal — Revised & Resubmitted

This package has been reorganized in response to the review comments received. The table below summarizes each comment and where it is addressed in this revision:

CM REVIEW COMMENT	RESPONSE / WHERE ADDRESSED
Information should be grouped per Residential Units and Corridors .	Package is now organized by location. Section 2 covers Residential Unit assemblies; Section 3 covers Corridor assemblies; Section 4 covers exterior/masonry furring common to both. See Table of Contents.
Do not include every item in the supplier brochures — only actual products to be used, tagged with location (wet walls, showers, bathrooms, regular areas, corridors, ceilings, etc.).	Section 1 — Master Material Location Schedule lists only the products to be installed on this project. Every product line carries its specific location(s) of use and the wall type tag(s) where it occurs. Every gypsum panel type states exactly where it goes.
No information was provided for insulation .	Tab 5 — Insulation: CertainTeed R-19 unfaced sound attenuation batts (corridor walls & unit demising walls) and Fi-Foil AA2 Vapor Shield reflective insulation ("ALFOIL" per A8.01, at furred exterior masonry walls). Manufacturer data sheets are bound in this package.
No information was provided for fire stopping (fire caulk / putty).	Tab 6 — Firestopping: USG Sheetrock® Brand Firecode® Smoke-Sound Sealant at rated partition perimeters, joints and cutouts, and intumescent firestop putty pads at electrical boxes in demising partitions (per General Notes). Product data included.
Show what will be installed in the building, properly marked for reviewer/consultant reference.	Section 2–4 provide an assembly cut sheet for each wall type with a section diagram, numbered material callouts, and a page reference into the manufacturer data portion of this book for every component. Wall type tags match the architectural plans (A8.01/A8.02).

How this book is organized: Sections 1–4 (this front book) are job-specific schedules and assembly cut sheets. Tabs 1–6 contain manufacturer product data, in the same order and page numbering as referenced from the assembly cut sheets ("Book pg." column). Appendices reproduce the governing architectural references (wall type sheet and a typical residential level plan).

Table of Contents

SUBMITTAL 09 29 00-01 REV. 1 — ORGANIZED BY LOCATION & SYSTEM

—	Cover Sheet — Project & Contact Information	i
—	Transmittal & Response to Review Comments	ii
S-1	Master Material Location Schedule — every product tagged with where it is used	iv
S-2	Wall Type Index & Location Key — plan tags → assemblies → products	vi
S-3	Residential Unit Assemblies — unit partitions, wet walls, tub/shower walls, demising walls, unit ceilings	vii
S-4	Corridor Assemblies — corridor walls & corridor ceilings	ix
S-5	Exterior & Masonry Wall Furring Assemblies — furred CMU walls, shafts & stairs	x
TAB 1	Metal Framing — manufacturer data	Book pg. 1–41
	Steel-Con studs, tracks, hat channel, angle & accessories — all framed walls, furring & ceilings, units + corridors	pg. 1–36
	Rescue Metal framing & accessories (alternate supplier, same profiles)	pg. 37–41
TAB 2	Gypsum Panels — Drywall & Finishing — manufacturer data	Book pg. 42–106
	United States Gypsum (USG) — primary panels & joint treatment — see S-1 for location of each panel type	pg. 42–78
	CertainTeed Gypsum — approved alternate, non-rated unit partitions/ceilings only	pg. 79–100
	Georgia-Pacific Gypsum — approved alternate, same locations as USG equivalents	pg. 101–102
	National Gypsum — approved alternate, same locations as USG equivalents	pg. 103–106
TAB 3	Corner Bead & Trim — all outside corners & exposed edges, units + corridors	Book pg. 107–114
	American Cornerbead Company	pg. 107–113
	Rescue Metal trims	pg. 114
TAB 4	Fasteners — all board & framing attachment, units + corridors	Book pg. 115–123
	Building Products of America drywall screws	pg. 115–116
	Starborn Industries fasteners	pg. 117–123
TAB 5	Insulation — corridor walls, unit demising walls, exterior furred masonry walls	Appendix C
	CertainTeed NoiseReducer™ R-19 unfaced sound attenuation batts — corridor walls & unit demising walls	C-1
	Fi-Foil AA2 Vapor Shield™ reflective insulation (“ALFOIL” per A8.01) — furred exterior masonry walls	C-2
TAB 6	Firestopping — Fire Caulk & Putty — all rated partition perimeters, joints, penetrations & boxes	Sect. S-6
	USG Sheetrock® Brand Firecode® Smoke-Sound Sealant — rated walls: corridors, demising, shafts	S-6
	Intumescent firestop putty pads — electrical boxes in demising partitions (per General Notes)	S-6
APP. A	Architectural Reference — Wall Types (A8.01, Concrete)	A-1
APP. B	Architectural Reference — Typical Residential Level Plan (Level 7, Stack A105)	B-1
APP. C	Insulation Manufacturer Data Sheets (bound herein)	C-1–C-3

Note to reviewer: “Book pg.” numbers refer to the manufacturer product data portion of this submittal book. Products shown in supplier literature but not listed in Schedule S-1 are not proposed for this project.

S-1 Master Material Location Schedule

ONLY PRODUCTS TO BE INSTALLED AT CLAUDE PEPPER — EACH TAGGED WITH ITS LOCATION OF USE

A. Gypsum Panels — where every sheet goes

PRODUCT	MFR.	SIZE / TYPE	LOCATION OF USE (TAGGED)	WALL TAGS	BOOK PG.
Sheetrock® Firecode® X (UL Type SCX)	USG	5/8" Type X	Regular areas in units (bedrooms, living, closets — both faces of interior partitions); both faces of demising walls; both faces of corridor walls; corridor ceilings; interior face of furred exterior walls (dry areas)	20, 21, 25, 10/15	42–78
Sheetrock® Mold Tough® Firecode® X (UL Type SCX)	USG	5/8" Type X, mold/moisture-resistant	Bathrooms & wet walls (all bathroom walls & ceilings, kitchen sink walls, laundry/washer walls, plumbing chases) — in lieu of standard panels per A8.01 note "Aqua Tough at shower and tub locations"	21a, 21b	42–78
Durock® Cement Board w/ EdgeGuard™	USG	1/2" cement board	Showers & tub surrounds — tile backer at all unit shower/tub wet zones, full height of tile	21b	42–78
Sheetrock® UltraLight	USG	1/2" sag-resistant	Unit ceilings (non-rated furred/suspended GWB ceilings within dwelling units, dry areas only; bathrooms use Mold Tough)	RCP	42–78
Sheetrock® Glass-Mat Liner Mold Tough® (UL Type SLX)	USG	1" shaftliner	Shaft walls — elevator shafts, stair shafts and MEP shaft enclosures where cavity shaft wall is indicated	per plan	42–78
Securock® UltraLight Glass-Mat Sheathing	USG	5/8" Type X	Exterior soffits & covered exterior ceilings where glass-mat sheathing substrate is required	per plan	42–78
Easi-Lite™ Lightweight Drywall (approved alternate only)	CertainTeed	1/2"	Alternate to USG UltraLight at non-rated unit ceilings / non-rated unit partitions only; not used in rated assemblies	RCP	79–100
Type X panels (approved alternates only)	Georgia-Pacific / National Gypsum	5/8" Type X	Approved equal alternates for the same tagged locations as USG Firecode X, subject to matching UL type in rated assemblies	20, 21, 25	101–106

B. Metal Framing (Steel-Con primary — Rescue Metal, book pg. 37–41, approved alternate for the same profiles & locations)

PRODUCT	MEMBER	LOCATION OF USE (TAGGED)	WALL TAGS	BOOK PG.
Studs 362S125 / 362SFS (25 ga eq. / D20)	3-5/8" stud	Unit interior partitions, demising walls, corridor walls @ 24" o.c. max (20 ga where over 10'-0" per GN)	20, 21, 25	14–20
Studs 600S125 / 600SFS	6" stud	Wet walls / plumbing walls in units and where 6" studs noted on plan (WT 3a/3c)	21a	14–20
Studs 162S125 / 162SFS	1-5/8" stud	Furring at exterior masonry walls, columns & shear walls (interior face, units & corridors)	10, 15	14–20
Tracks 162T / 362T / 600T (& SFT)	Top & bottom track	Matching size at top/bottom of every framed wall above , fastened 24" o.c. max per A8.01	all	6–13
Hat channel 087F125, angle & flat stock	7/8" hat channel + accessories	Unit & corridor GWB ceilings; furring at CMU; ceiling perimeters, blocking/backing & bracing	RCP	21–26

S-1 Master Material Location Schedule (cont.)

FINISHING, INSULATION & FIRESTOPPING

C. Joint Treatment, Trim & Fasteners

PRODUCT	MFR.	LOCATION OF USE (TAGGED)	BOOK PG.
Sheetrock® All Purpose Joint Compound	USG	Taping & finishing of all GWB surfaces — units, corridors & ceilings (Levels of finish per GA-214)	42–78
Sheetrock® Easy Sand™ Setting-Type Compound	USG	Fire-taping of rated assemblies, prefill & patches — corridors, demising, shafts	42–78
Sheetrock® Heavy Joint Tape	USG	All GWB joints — units + corridors	42–78
Corner bead & trims	American Cornerbead / Rescue	All outside corners, exposed board edges & control joints — units + corridors	107–114
Drywall screws (Type S, S-12) & framing fasteners	BPA / Starborn	All board-to-stud & framing attachment ; cement-board screws at Durock (showers/tubs)	115–123

D. Insulation (Tab 5 / Appendix C — data sheets bound in this package)

PRODUCT	MFR.	LOCATION OF USE (TAGGED)	REF.
NoiseReducer™ R-19 Unfaced Sound Attenuation Batts (6-1/4" × 24", ASTM C665 Type I, unfaced — FS 25 / SD 50)	CertainTeed	Corridor walls (tag 20) and unit-to-unit demising walls (tag 25) — friction-fit full height between studs, full coverage, both for STC performance and per plan	C-1
AA2 Vapor Shield™ Reflective Insulation ("ALFOIL INSULATION" per A8.01; tape-tab for metal framing)	Fi-Foil	Furred exterior masonry walls — between 1-5/8" furring/studs at interior face of exterior CMU, units & corridors (WT 5a/5b, 9a & similar); FBC-compliant reflective insulation, R-5.1+ at 1-1/2"–1-5/8" cavity	C-2

E. Firestopping — Fire Caulk & Putty (Tab 6 / Section S-6)

PRODUCT	MFR.	LOCATION OF USE (TAGGED)	REF.
Sheetrock® Brand Firecode® Smoke-Sound Sealant (acrylic latex; ASTM C834; E84 FS 0 / SD 0)	USG	All rated & sound-rated partitions : continuous beads at top-of-wall & bottom-of-wall runners, partition perimeters & intersections, and around all cutouts (boxes, penetrations) at corridor walls, demising walls & shaft walls , per listed joint systems	S-6
Intumescent Firestop Putty Pads	UL-listed (STI SpecSeal® SSP or equal)	Electrical outlet boxes in demising partitions — wrap all boxes per project General Notes; membrane-penetration protection in rated walls	S-6
GrabberGard firecaulk (superseded)	Grabber	Included in original book pg. 124–127 — replaced in this revision by USG Firecode Smoke-Sound Sealant above ; retained only as approved-equal reference	124–127

Fire-safing per General Notes: Fire and smoke barrier caulk or putty, fire barrier partitions and covers, complete with necessary clips, supports and fastenings, shall meet a 2-hour fire rating for floors/roofs and the rating of the fire wall. All materials are UL Building Materials Directory listed (fill/void/cavity materials and through-penetration firestop systems).

S-2 Wall Type Index & Location Key

PLAN TAGS → LOCATION → ASSEMBLY CUT SHEET (MATCHES A8.01 / A8.02 & LEVEL PLANS)

PLAN TAG	ASSEMBLY	WHERE IT OCCURS	RATING	INSULATION	CUT SHEET
21	Unit interior partition — 3-5/8" (or 1-5/8" per plan) studs, 5/8" GWB e.s.	Residential units — regular areas	Non-rated	—	S-3.1
21a	Unit wet wall — 6" studs at plumbing, Mold Tough panels	Units — bathrooms, kitchen sink & laundry walls	Non-rated	—	S-3.2
21b	Tub/shower wall — Durock at tile, Mold Tough balance	Units — showers & tub surrounds	Non-rated	—	S-3.3
25	Unit demising wall — studs, 5/8" Firecode X e.s., sound batts	Unit-to-unit separation	1-hr / STC per plan	R-19 SAB	S-3.4
20	Corridor wall — studs, 5/8" Firecode X e.s., sound batts	Unit-to-corridor separation	1-hr / STC per plan	R-19 SAB	S-4.1
10 / 15	Furred exterior/masonry wall — 1-5/8" furring, AA2, 5/8" GWB	Exterior walls & shear walls/columns — units & corridors	CMU 2-hr (UL U905)	Fi-Foil AA2	S-5.1
WT 1–3	Interior framed partitions per A8.01 (1-5/8", 3-5/8", 6" studs)	Common areas per plan	Per A8.01	—	S-3.1
WT 4–6, 9, 10	Masonry walls, exposed or furred, stucco where noted	Exterior, garage & core	2–3-hr (UL U905/U907)	AA2 where furred	S-5.1
Shafts	Cavity shaft wall — CT studs, 1" SLX liner + 5/8" Firecode X	Elevator/stair/MEP shafts	2-hr	—	S-5.2

Coordination note: Framed wall type tags (15, 20, 21-series, 25) are per the architectural framing wall type sheet A8.02 and level plans; concrete/masonry types per A8.01 (reproduced in Appendix A). Stud gauge upgrades per General Notes: 20 ga where partitions exceed 10'-0" or support cabinetry/fixtures; 18 ga at exterior soffits @ 16" o.c.

Location legend used throughout this package

LOCATION TAG	MEANING
Regular areas in units	Bedrooms, living/dining, closets, entry — dry interior partitions and walls within dwelling units
Wet walls	Walls containing or backing plumbing: bathroom walls, kitchen sink walls, laundry walls, plumbing chases
Showers / tubs	Walls enclosing shower stalls and tub surrounds, to full height of tile
Bathrooms	All walls & ceilings within bathrooms (moisture-resistant panels throughout)
Demising walls	Unit-to-unit separation walls (tag 25)
Corridors	Unit-to-corridor walls (tag 20), corridor faces & corridor ceilings
Ceilings	GWB ceilings: UltraLight in unit dry areas, Mold Tough in bathrooms, Firecode X at corridors & where rated
Exterior walls	Furred interior face of exterior CMU walls (Fi-Foil AA2 + 5/8" GWB per A8.01)


S-3 Residential Unit Assemblies

GROUP 1 OF 3 — EVERYTHING INSTALLED INSIDE THE DWELLING UNITS

21

S-3.1 UNIT INTERIOR PARTITION — REGULAR AREAS

BEDROOMS • LIVING • CLOSETS
ALL DWELLING UNITS, TYP. ALL LEVELS



PLAN SECTION — N.T.S.

Ref. A8.01 WT 2/3 & plan tag 21


#	COMPONENT	PRODUCT SUBMITTED	BOOK PG.
1	Gypsum board, each side	(1) layer 5/8" USG Sheetrock® Firecode® X	42-78
2	Studs @ 24" o.c. max	Steel-Con 362S125 (3-5/8") or 162S125 (1-5/8") — size per plan; 25 ga eq. (≤10'-0"), D20/20 ga (>10'-0" or fixture support)	14-20
3	Top & bottom track	Steel-Con 362T125 / 162T125, fastened to structure @ 24" o.c. max	6-13
	• Joint treatment	USG Heavy Joint Tape + All Purpose / Easy Sand™	42-78
	• Corner bead / fasteners	American Cornerbead; BPA/Starborn Type S screws	107-123

Base as scheduled. At shower/tub locations this assembly transitions to **S-3.3**.

21a

S-3.2 UNIT WET WALL / PLUMBING WALL

BATHROOM & KITCHEN SINK WALLS • LAUNDRY
ALL DWELLING UNITS



PLAN SECTION — N.T.S.

6" studs at plumbing runs per plan (WT 3a/3c)

#	COMPONENT	PRODUCT SUBMITTED	BOOK PG.
1	Gypsum board, each side	(1) layer 5/8" USG Sheetrock® Mold Tough® Firecode® X — all bathroom & plumbing-side faces	42-78
2	Studs @ 24" o.c. max	Steel-Con 600S125 (6") at plumbing walls; 362S125 elsewhere per plan	14-20
	• Track / joint / trim / fasteners	Matching Steel-Con track; USG joint treatment; American Cornerbead; BPA/Starborn screws	6-13, 42-78, 107-123

Moisture-resistant panels carried throughout **bathrooms (walls & ceilings)**, kitchen sink walls and laundry walls.


S-3 Residential Unit Assemblies (cont.)

SHOWERS/TUBS & UNIT-TO-UNIT DEMISING

21b

S-3.3 TUB & SHOWER WALLS

SHOWER STALLS & TUB SURROUNDS
ALL UNIT BATHROOMS



PLAN SECTION AT SHOWER — N.T.S.

Per A8.01 note: moisture-resistant board at shower & tub locations


#	COMPONENT	PRODUCT SUBMITTED	BOOK PG.
1	Tile (by others) over tile backer	—	—
2	Tile backer, wet-zone face	1/2" USG Durock® Cement Board w/ EdgeGuard™, cement-board screws, joints per mfr.	42-78
3	Balance of wall / opposite face	5/8" USG Sheetrock® Mold Tough® Firecode® X	42-78
•	Framing	Steel-Con studs & track per S-3.1/S-3.2 (16" o.c. at cement board)	6-20

A8.01 calls "USG Aqua Tough drywall at shower and tub locations" — submitted herein as USG's current equivalents: **Durock® cement board at tiled wet zones** and **Mold Tough® panels** at remaining bathroom surfaces.

25

S-3.4 UNIT DEMISING WALL (UNIT-TO-UNIT)

BETWEEN DWELLING UNITS, TYP.
ALL RESIDENTIAL LEVELS



PLAN SECTION — N.T.S.

Rated + sound-insulated; see plan for rating & UL design

#	COMPONENT	PRODUCT SUBMITTED	BOOK PG.
1	Gypsum board, each side	(1) layer 5/8" USG Sheetrock® Firecode® X (UL Type SCX), fire-taped; layers per UL design on plan	42-78
2	Studs @ 24" o.c. max	Steel-Con 362S125 / 362SFS-D20, size per plan	14-20
3	Sound attenuation insulation	CertainTeed NoiseReducer™ R-19 unfaced batts , 24" wide, friction-fit full height — full coverage	C-1
4	Perimeter seal & boxes	USG Firecode® Smoke-Sound Sealant at runners/perimeter/cutouts; putty pads at electrical boxes (per GN)	S-6

UL: assembly rating & design number per plan wall schedule (Type SCX panels usable in any UL design listing SCX). Electrical outlets in demising partitions receive firestop putty pads — no exclusions.


S-4 Corridor Assemblies

GROUP 2 OF 3 — UNIT-TO-CORRIDOR WALLS & CORRIDOR CEILINGS

20

S-4.1 CORRIDOR WALL (UNIT-TO-CORRIDOR)

BOTH SIDES OF ALL RESIDENTIAL CORRIDORS
TYP. ALL LEVELS



Rated corridor separation w/ sound batts (per TruTeam insulation submittal)


#	COMPONENT	PRODUCT SUBMITTED	BOOK PG.
1	Gypsum board, each side	(1) layer 5/8" USG Sheetrock® Firecode® X (UL Type SCX), fire-taped; layers per UL design on plan	42-78
2	Studs @ 24" o.c. max	Steel-Con 362S125 / 362SFS-D20 (20 ga where >10'-0")	14-20
3	Sound attenuation insulation	CertainTeed NoiseReducer™ R-19 unfaced batts, friction-fit full height — full coverage	C-1
4	Perimeter seal	USG Firecode® Smoke-Sound Sealant continuous at top/bottom runners, perimeter & all cutouts	S-6

Corridor walls maintain continuity to deck; head-of-wall joints sealed per listed joint system.

CLG

S-4.2 CORRIDOR CEILING

ALL RESIDENTIAL CORRIDORS
PER RCP



Framing & suspension per plan/RCP details

#	COMPONENT	PRODUCT SUBMITTED	BOOK PG.
1	Furring / suspension	Steel-Con 087F125 hat channel & angle, spacing per RCP details	21-26
2	Ceiling board	5/8" USG Sheetrock® Firecode® X, finished per GA-214	42-78

Unit ceilings (for comparison): 1/2" USG Sheetrock® UltraLight at dry areas; 5/8" Mold Tough® at bathroom ceilings; rated ceilings per RCP keep 5/8" Firecode X.

S-5 Exterior & Masonry Wall Furring Assemblies


GROUP 3 OF 3 — FURRED CMU WALLS (UNITS & CORRIDORS) AND SHAFT WALLS

10/15

S-5.1 FURRED EXTERIOR / MASONRY WALL

INTERIOR FACE OF EXTERIOR CMU WALLS, SHEAR
WALLS & COLUMNS — UNITS & CORRIDORS

EXTERIOR CMU



PLAN SECTION — N.T.S.

Per A8.01 WT 5a/5b, 9a — CMU UL U905 (2-hr) / U907 (3-hr at B-4 filled cell)

#	COMPONENT	PRODUCT SUBMITTED	BOOK PG.
1	Gypsum board	(1) layer 5/8" USG Sheetrock® Firecode® X (dry areas); Mold Tough® at bathrooms; per A8.01 note, moisture-resistant board at shower/tub locations	42-78
2	Reflective insulation ("ALFOIL")	Fi-Foil AA2 Vapor Shield™ , tape-tab, installed across furring per mfr. (R-5.1+ at 1-1/2"–1-5/8" cavity, 24" o.c.)	C-2
3	Furring @ 24" o.c. max	Steel-Con 162S125 (1-5/8") or 362S125 (3-5/8") per plan; matching track top & bottom @ 24" o.c.	6-20


UL: masonry wall bearing/nonbearing rating 2-HR — **UL U905**; 8" B-4 filled-cell block 3-HR — **UL U907** (per A8.01). Stucco at exterior face by others.

SHAFT

S-5.2 CAVITY SHAFT WALL (WHERE FRAMED SHAFTS OCCUR)

ELEVATOR • STAIR • MEP SHAFTS
PER PLAN

1" LINER



Only where framed shaft walls are indicated; masonry shafts per S-5.1

#	COMPONENT	PRODUCT SUBMITTED	BOOK PG.
1	Shaft liner	1" USG Sheetrock® Glass-Mat Liner Mold Tough® (UL Type SLX) or Mold Tough® Gypsum Liner	42-78
2	C-T / C-H studs & J-runners	USG shaft wall framing components (with SLX-listed systems)	42-78
3	Face layer(s), occupied side	5/8" USG Sheetrock® Firecode® X, layers per UL design (2-hr)	42-78

Perimeter joints sealed with USG Firecode® Smoke-Sound Sealant per S-6.

S-6 Firestopping — Fire Caulk & Putty (Tab 6)

PRODUCT DATA — USG SHEETROCK® BRAND FIRECODE® SMOKE-SOUND SEALANT & FIRESTOP PUTTY PADS

USG Sheetrock® Brand Firecode® Smoke-Sound Sealant

One-product acrylic latex sealant for fire, smoke and sound control in rated partitions, smoke barriers and sound-rated assemblies. (USG submittal J2042 — official manufacturer sheet to accompany this tab.)

PROPERTY	VALUE
Type	Acrylic, latex-based fire/smoke/sound sealant
Color	Rust red (easy identification by inspectors)
Specification compliance	ASTM C834 (latex sealing compounds); tested per ASTM C731, C732, C734, C736, D2202, D2203, D2377
Surface burning (ASTM E84)	Flame spread 0 • Smoke developed 0 (UL Classified)
Sound (ASTM E90)	Maintains high STC ratings as sound-flanking sealant in rated partitions
Joint systems (ASTM E1966 / UL 2079)	For use in listed head-of-wall / perimeter joint systems
Sustainability	GREENGUARD Gold certified, low-VOC
Packaging	29 oz. cartridges (standard caulking gun; vertical or horizontal beads, non-sag)

Where used on this project

LOCATION	APPLICATION
Corridor walls (tag 20)	Continuous bead at top & bottom runners, wall perimeter, intersections, all cutouts
Demising walls (tag 25)	Same as above; plus bead around boxes ahead of putty pads
Shaft walls	Perimeter joints at J-runners & deck
Sound-rated assemblies	All assembly cutouts (electrical boxes, penetrations) per USG sound-control details

Intumescent Firestop Putty Pads

UL-listed moldable intumescent putty pads (STI SpecSeal® SSP or approved equal), applied to the exterior of electrical boxes in rated walls.

PROPERTY	VALUE
Use	Membrane-penetration protection at outlet/switch boxes in rated gypsum assemblies
Listing	UL Classified, fill/void/cavity material — UL Building Materials Directory
Project requirement	Per General Notes: “Electrical outlets in demising partitions shall have fire stop putty pads installed” — no exclusions

General Notes compliance (fire safing)

Fire & smoke barrier caulk or putty, fire barrier partitions and covers, complete with clips, supports and fastenings, meet a **2-hour rating for floors and roofs** and the **rating of the fire wall**. All materials listed in the **UL Building Materials Directory**: fill, void or cavity materials, and through-penetration firestop systems. All penetrations located within rated partitions are fire-rated — no exclusions.











Supersedes: Grabber firecaulking data at book pg. 124–127 (Rev. 0). USG Firecode® Smoke-Sound Sealant is the product to be installed; Grabber retained as approved-equal reference only.

APPENDICES

Architectural References & Insulation Data Sheets

APPENDIX	CONTENTS
A	Wall Types — Concrete (Sheet A8.01, Cohen-Freedman-Encinosa & Assoc.) — governing assembly details & UL designs referenced by cut sheets S-3 to S-5
B	Typical Residential Level Plan — Level 7, Stack A105 — showing wall type tags (20, 21, 21a, 21b, 25) at Units A1 / B1-R and corridor
C	Insulation manufacturer data: C-1 CertainTeed NoiseReducer™ R-19 unfaced sound attenuation batts (corridor & demising walls) • C-2 Fi-Foil AA2 Vapor Shield™ (furred exterior masonry walls)

Manufacturer product data for framing, gypsum panels, trims and fasteners follows under Tabs 1–4 (book pages 1–123).



TO THE BEST OF OUR KNOWLEDGE
THE PLANS AND SPECIFICATIONS
COMPLY WITH THE APPLICABLE
MINIMUM BUILDING CODES AND
THE APPLICABLE FIRE SAFETY
STANDARDS AS DETERMINED BY
THE LOCAL AUTHORITY IN
ACCORDANCE
WITH CHAPTER 553 AND CHAPTER


COHEN • FREEDMAN • ENCINOSA & ASSOC.
Architects, PA AA C000779
8085 N.W. 155th Street Miami Lakes, Florida 33016
305 826 3999

Project name: **THE RESIDENCES CLAUDE PEPPER**
750 NW 18TH TERRACE, MIAMI FL 33136
- WALL TYPES - CONCRETE

SANDY L. PEACEMAN STATE OF FLORIDA REGISTERED ARCHITECT AR# 0016169	ARTURO L. ROBINSON STATE OF FLORIDA REGISTERED ARCHITECT AR# 0016169
--	---

[illegible]

Drawn by:	CFE
Date:	09.15.25
Sheet no:	A8.01
Project:	4017



NoiseReducer™ Sound Attenuation and Acoustical Ceiling Batts

PRODUCT DESCRIPTION

Basic Use: These products are designed for use in commercial and residential wall and ceiling assemblies to effectively reduce transmission of airborne sound and provide thermal insulation.

Benefits: They provide excellent acoustical performance to help reduce sound transmission between adjoining rooms. These lightweight, flexible products are easy to handle and fabricate on the job site and conform to irregular surfaces. The product resists mold and mildew and will not rot or deteriorate.

Composition and Materials: The product is composed of tan, uniformly textured, inorganic fibrous glass and formed with a formaldehyde-free binding agent. Sound Attenuation Batts are available unfaced for friction fit installation between studs or Kraft faced for easy positive attachment to interior wood stud framing. Acoustical Ceiling Batts are available unfaced and Kraft faced (without stapling tabs) for installation on suspended ceilings.

Limitations: The National Electrical Code prohibits installation of any insulation over or within 3" (76 mm) of recessed light fixtures, unless approved insulated ceiling (IC) lighting fixtures are used.

Standard Kraft facing is flammable and should not be left exposed. Kraft faced insulation must be installed behind and in substantial contact with the unexposed surface of the ceiling, floor or wall finish. Special care should be taken when working with an open flame. Where a flame spread rating of 25 is required, insulation must be unfaced or have flame-resistant foil facing (FSK-25).

Because of potential skin irritation, unfaced building insulation should not be installed in an exposed application where it will be subject to human contact.

All building insulation should be kept dry. Wet fiber glass insulation will lose its effectiveness until it dries. Fiber glass will often dry naturally and regain its original R-Value. However, under conditions where the insulation will not dry thoroughly, it should be removed and replaced.

Sizes: Available standard sizes are listed in table on other side. Contact CertainTeed for non-standard sizes.

INSTALLATION

For most areas, vapor retarders should be installed on the warm-in-winter side of the insulation (toward the interior). Check local practice and/or building codes. CertainTeed insulation is not intended to be installed with the facing placed toward the exterior of the building.

Requirements for installation:

- Unfaced Sound Attenuation Batts – Friction fit between steel studs. (Supplementary support may be required for floor/ceiling installations.)
- Acoustical Ceiling Batts – Lay faced or unfaced batts directly on suspended ceilings. (Check with ceiling panel manufacturer for weight limitations.)
- Interior Wall (white) Kraft Faced Batts – Staple flanges to either the faces or sides of studs or joists using enough staples to prevent gaps. Do not leave the facing exposed; see limitations above.



Product Name	NoiseReducer™ Sound Attenuation and Acoustical Ceiling Batts
Manufacturer	CertainTeed Corporation
Address	P.O. Box 860 Valley Forge, PA 19482-0105
Phone	610-341-7000 • 800-233-8990
Fax	610-341-7571
Website	www.certainteed.com/insulation

TECHNICAL DATA

Applicable Standards

- Model Building Codes:
 - ICC
 - California and Minnesota Quality Standards
- Material Standards:
 - ASTM C553, Type I, II
 - ASTM C665, Type I, unfaced
 - ASTM C665, Type II, Class C, Category 1, Kraft Faced
- GREENGUARD® Children & Schools Certified

Fire Resistance

- Fire Hazard Classification:
 - ASTM E84
Unfaced insulation:
Max. Flame Spread Index: 25
Max Smoke Developed Index: 50
Kraft faced insulation: Not rated for flame spread/smoke developed
- Noncombustibility: ASTM E136
Unfaced insulation / Pass

Physical/Chemical Properties

- Thermal Performance:
 - ASTM C 518 / R-Values for insulation only, as stated in table on other side.
- Water Vapor Sorption:
 - ASTM C1104 / ≤ 5%
- Water Vapor Permeance:
 - Permeance of Kraft Facing: ASTM E96, Desiccant method
≤ 1.0 perm (57 ng/Pa•s•m²)
 - Class II vapor retarder

Quality Assurance

CertainTeed's commitment to quality and environmental management has ensured the registration of the Athens, Chowchilla and Kansas City plants to ISO 9001:2000 and ISO 14001:2004 standards.

AVAILABILITY AND COST

For availability and cost, contact your local contractor or distributor, or call CertainTeed Sales Support Group at 800-233-8990.

WARRANTY

Refer to CertainTeed's Lifetime Limited Warranty for Fiber Glass Building Insulation (30-21-1321).

MAINTENANCE

No maintenance required.

TECHNICAL SERVICES

Technical assistance can be obtained either from the local CertainTeed sales representative, or by calling CertainTeed Sales Support Group in Valley Forge, PA at 800-233-8990.

SOUND ATTENUATION BATTS

AVAILABLE SIZES						
R-Value		Thickness		Width		Facing
R	RSI	in.	mm	in.	mm	
8	1.4	2 ½	64	16	406	Unfaced
8	1.4	2 ½	64	24	610	Unfaced
11	1.9	3 ½	89	16	406	Unfaced
11	1.9	3 ½	89	24	610	Unfaced
11	1.9	3 ½	89	24	610	Kraft (no tabs)
11	1.9	3 ½	89	15	381	Kraft
11	1.9	3 ½	89	23	584	Kraft
11	1.9	3 ½	89	24	610	Unfaced
19	3.3	6 ¼	159	24	610	Unfaced
19	3.3	6 ¼	159	24	610	Kraft (no tabs)



ASK ABOUT OUR OTHER CERTAINTEED PRODUCTS AND SYSTEMS:

ROOFING • SIDING • TRIM • DECKING • RAILING • FENCE • FOUNDATIONS
GYPSUM • CEILINGS • INSULATION • PIPE

CertainTeed Corporation
P.O. Box 860
Valley Forge, PA 19482


Professional: 800-233-8990
Consumer: 800-782-8777
www.certainteed.com/insulation

CertainTeed
SAINT-GOBAIN



Specification Sheet

Fi-Foil AA2 Vapor Shield™ is a reflective insulation intended for use on furred-out masonry walls. The inside layer is aluminum foil. The outer layer is natural Kraft paper coated with polyethylene, laminated to flange boards or expanders that separate paper from foil creating a reflective air space. When installed on furring strips spaced 16" or 24" on center, a second reflective air space is formed. This air space is dependent upon the thickness of the furring strip selected. The Hi-Perm version includes small perforations for applications not requiring a vapor retarder. Available in both staple tab (for wood furring) and tape tab (for metal framing).



Definition of Reflective Insulation

Reflective insulation is used to reduce the transport of energy across air spaces in a building envelope and consists of one or more low emittance surfaces (0.10 or less), bounding one or more enclosed air spaces. Reflective insulation can also use other layers of materials such as paper or plastic to form enclosed air spaces as part of the system. The performance of the reflective insulation system is determined by the emittance of the material(s), the lower the better, and the size of the enclosed air spaces. The smaller the enclosed air space, the less heat will transfer by convection. Reflective insulation is recognized by ASTM, The Federal Trade Commission and Code Bodies as an accepted insulation technology. R-values can be both tested or calculated using established ASTM standards.

Product Information

Furring/Stud	16" O.C.	24" O.C.
Width Expanded	17.5"	25.5"
Diameter	10"	8"
Lineal Footage	375'	250'
Coverage	500 sq. ft.	500 sq. ft.
Weight	21 lbs.	19 lbs.

R-Values

Heat Flow Horizontal

	Standard	Hi-Perm
3/4" Cavity	R- 4.2	R- 4.1
7/8" Cavity	R- 4.5	R- 4.6
1-1/2" to 1-5/8" Cavity	R- 5.2	R- 5.1

ASTM C -236 R-Value Test. The R-values of AA2 Vapor Shield™ increase with the thickness of furring strips. With the use of AA2 Vapor Shield™, the thickness of furring strips are slightly increased because it is applied to the surface of the strips and overlaps. Therefore all measurements are considered nominal.

Test Data

Product Version	Perforated	Non-Perforated
ASTM E 96 Water Vapor Permeance	4.72	0.802
ASTM E 84-94 Flammability		
Flame Spread Rating	45	45
Smoke Developed Rating	10	10
National Fire Protection Association Rating	Class B	Class B
ASTM D 3310 Corrosivity.....	None	
ASTM C 1224/Section 9 Adhesive Performance		
Bleeding.....	None	
Delamination.....	None	
Pliability.....	No signs of cracking or delamination	
ASTM C 1338 Mold & Mildew	Pass	
ASTM C 1371 Foil Emittance.....	0.03	

Compliance and Approvals

- Meets: ASTM C1224
- Compliance with the following code *
 - 2012, 2009, and 2006 International Building Code (IBC)
 - 2012, 2009, and 2006 International Residential Code (IRC)
 - 2012, 2009, and 2006 International Energy Conservation Code (IECC)
 - 2010 and 2007 Florida Building Code (FBC)
 - 2010 and 2007 Florida Residential Code (FRC)
 - 2010 and 2007 Florida Energy Conservation Code (FECC)
- Evaluated in accordance with *
 - ICC-ES AC 02 - Acceptance Criteria for Reflective Insulation, approved June 2011
- State of California Bureau of Home Furnishings and Thermal Insulation License #T1390, Registry #CA-T390 FL

* See IAMPO-ES Report #0291

High Recycled Content

Certified by a third party testing and inspection service (R&D Services, Inc.), Reflective Insulation has more than 44 percent recycled content, with at least 42 percent being post-consumer content.

16" AA2	More than 44% Recycled Content
24" AA2	More than 44% Recycled Content

Read This Before You Buy

The label shows the R-value of the insulation. R means resistance to heat flow. The higher the R-value, the greater the insulating power. Compare insulation R-values before you buy. There are other factors to consider. The amount of insulation you need depends mainly on the climate you live in. Also, your fuel savings from insulation will depend on the climate, the type and size of your house, and your fuel use patterns and family size. If you buy too much insulation, it will cost you more than what you will save on fuel. To get the marked R-value, it is essential that this insulation be installed properly.